



PRESTON PUBLIC SCHOOLS  
1 Route 164  
Preston, Connecticut 06365

## Addendum No. 1 June 15, 2018

1. **DESCRIPTION OF WORK** - Remove approximately 37,000 sq. ft. of existing black top. Regrade and pave with 3" Class 2 asphalt. (Per Diagram).

Also:

- I. Two layers should be applied.

Layer A 2 and ½ inches rolled to 2 inches

Layer B 1 inch finished

- II. Replace two catch basin tops

## 2. **PROPOSAL SPECIFICATIONS**

**Specification No. 4 (Trench Alternate)**

delete 1,380 ft. replace with 138 ft.